


# TEMPORARY OVERHEAD SERVICE SUPPORT



**NOTES:**

1. **CUSTOMER** SHALL CONSULT WITH COMPANY FOR LOCATION OF TEMPORARY SERVICE POLE. SUCH POLE SHALL BE LOCATED NOT LESS THAN 10' OR MORE THAN 75' FROM COMPANY'S TRANSFORMER SECONDARY, UNLESS OTHERWISE APPROVED BY COMPANY. **CUSTOMER** MAY BE REQUIRED TO FURNISH AND INSTALL PROPER GUYING. COMPANY WILL BOND GUY TO SERVICE NEUTRAL. ALSO, **CUSTOMER** SHALL PAY APPLICABLE CHARGES.
2. ALL **CUSTOMER** WORK SHALL BE COMPLETED AND INSPECTIONS OBTAINED (SEE SECTION 4.06) BEFORE COMPANY WILL PROVIDE SERVICE.
3. SERVICE POLE OR SUPPORT, FURNISHED AND INSTALLED BY **CUSTOMER**. REQUIREMENTS: 18' MINIMUM LENGTH CHEMICAL PRESERVATIVE TREATED POLE OR 18' MINIMUM CONTINUOUS LENGTH 6" X 6" CHEMICAL PRESERVATIVE TREATED TIMBER FREE OF UNACCEPTABLE DEFECTS, INSTALLED MINIMUM 4' IN GROUND AND WELL TAMPED.
4. **INHIBITOR COMPOUND** SHALL BE USED ON ALL ALUMINUM WIRE TERMINATIONS.
5. COMPLETE **CUSTOMER** POLE INSTALLATION SUBJECT TO COMPANY APPROVAL PRIOR TO CONNECTION.